

Kansas Corporation Comm.
Wichita State Office Bldg.
-130 S. Market, Room 2078
Wichita. KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

WELL NUMBER 179-21082 0000

LEASE NAME Reidel

WELL NUMBER 1

4780 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 15 TWP. 9S RGE. 26 (E) or (W)

COUNTY Sheridan

Date Well Completed 1/7/96

Plugging Commenced 2:15PM 1/7/96

Plugging Completed 4:15PM 1/7/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR LESTER SENESAC OIL & GAS EXPLORATION

ADDRESS P.O. Box 305 Hill City, Kansas 67642

PHONE# (913) 674-2298 OPERATORS LICENSE NO. 31701

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/5/96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4118

Show depth and thickness of all water, oil, and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	250	8 5/8	250.28	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
1st Plug @ 2340' w/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/ 50 vis Mud
2nd Plug @ 1350' W/100sks 15sks In Rat Hole Plugs displaced with mud
3rd Plug @ 300' w/40sks
4th Plug @ 40' w/10sks 200sks Total 60/40 Poz 6%Gel w/1/4#FS/sk By Allied Cementing
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lester Senesac Oil & Gas Exploration

STATE OF Kansas COUNTY OF Graham, ss.

Lester V Senesac (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed: the
the same are true and correct, so help me God.

(Signature) Lester V Senesac

(Address) P.O. Box 305 Hill City KS 67642

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1996

Rita A. Anderson
Notary Public

My Commission Expires: January 21, 2000

