

15-179-00190-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County. Sec. 19 Twp. 9S Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SWSWSW

Lease Owner W. W. Sauvage

Lease Name Transue Well No. 1

Office Address Oberlin, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 11 19 57

Application for plugging filed July 11 19 57

Application for plugging approved July 11 19 57


Plugging commenced July 11 19 57

Plugging completed July 11 19 57

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud on bottom -- pulled pipe to 1500 feet and circulated with heavy mud. Pulled pipe set plug 210 feet. Mixed 20 sx cement 1/2 sx hulls, through drill pipe and filled hole with heavy mud to 40 feet. Set plug. 10 sx cement 1/2 sx hulls. Filled surface casing to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1957
CONSERVATION DIVISION
Wichita, Kansas
07-18-1957

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sauvage and Dunn Drilling Company, Inc.
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decatur, ss.
Opal Sauvage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Opal Sauvage
Oberlin, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 57



24-7366-5 3-53-20M

PLUGGING
FILE SEC 19 T 9 P 26W
BOOK PAGE 27 L 9

Notary Public.

15-179-00190-00-00

Drillers Log

Operator: W. W. Sauvage
Farm Name: Transue
Well No: 2
Contractor: Sauvage & Dunn Drlg. Co., Inc.
Rotary Commenced: June 20, 1957
Rotary Completed: July 11, 1957

Location: SWSWSW 19-9S-26W
Sheridan County, Kansas
Casing Record: 218 ft. 8 5/8 csg.
135 sx cement

Figures denote bottom of formation

Cellar	5
Sand and Flint Rock	200
Blue Shale	218
Shale	1040
Shale	1120
Shale and Sand	1740
Shale and Shells	2110
Lime and Shale	2276
Shale w/anhydrite	2290
Shale and anhydrite	2310
Shale and lime w/sand	2400
anhydrite	2425
Shale and sand--lime	2435
Shale and lime	2600
Lime and shale	2680
Sand and shale	2750
Lime and shale w/sand	2805
Lime and shale	2955
Lime	2985
Lime	3040
Lime and shale	3215
Lime and shale	3250
Lime and shale	3295
Sand and shale	3305
Lime and shale	3372
Lime and shale	3390
Lime and shale	3530
Lime	3640
Lime and shale	3717
Lime	3805
Lime	3831
Lime	3845
Lime -- broken	3890
Lime	3928
Lime	3990
Lime and shale	4020
Lime and shale	4095
Lime and shale	4110
Broken shale	4172
Shale and lime	4198
Shale and lime	4250
Lime and shale	4292
Shale, lime and chert	4392
Chert	4395
Chert	4415
Chert	4440
Lime w/chert	4455
Lime w/chert	4480


STATE OF KANSAS
JUL 18 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 19 T. 9 S. 26W
BOOK PAGE 27 LINE 9

State of Kansas
County of Decatur

I hereby certify that the foregoing is, to the best of my knowledge and belief a full, true and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

Opal Sauvage
For Sauvage & Dunn Drlg. Co., Inc.



Subscribed to and sworn to before me, the undersigned, a Notary Public, this 16th day of July, 1957.

Callum Kotke
Notary Public

My Commission expires 2-14-59