

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 179-20 911-00-00

LEASE NAME SIMON

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4950 Ft. from S Section Line

4950 Ft. from E. Section Line

SEC 20 TWP. 9S RGE. 26 (E) or (W)

LEASE OPERATOR Burch Exploration INC

ADDRESS 11225 Edinborough Way PARKER, Colo. 80138 COUNTY SHERIDAN

PHONE 303 841-9417 OPERATORS LICENSE NO. 7448

Date Well Completed 1-16-1988

Character of Well D+A

Plugging Commenced 1-16-1988

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-16-1988

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? HAYS, KANSAS

Is ACO-1 filed? YES If not, is well log attached? YES

Producing Formation KANSING K.C. Depth to Top 38'19" Bottom 4051' T.D. 4110

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>SAND</u>	<u>0</u>	<u>322</u>	<u>8 5/8</u>	<u>NEW</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran Drill Pipe to 2300' pump 10 BBLs. H2O SPACER MIX 25 SKS 60/40 PZ MIX 170 gal. Run 3 1/2" BBL. SPACER DISPLACE W/ Mud BALANCE. Pull Drill Pipe to 1050' 10 BBLs. H2O SPACER MIX 100 SKS PZ MIX 670 gal. W/ SK HIGH SEAL 3 1/2" BBLs OF Mud BALANCE. Pull Drill Pipe to 325' 100 SKS 60/40 PZ MIX 670 gal. PLUG Plug to 40'. Fill to SURFACE Plug Mouse Hole + Rat Hole w/ 100 SKS. Fill to SURFACE. Job Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Golden Eagle Drilling INC License No. 8682

Address P.O. BOX 983 Mc Cook, NE. 69001

STATE OF NEBRASKA COUNTY OF Red Willow, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

RECEIVED
 STATE CORPORATION COMMISSION

(Signature) J. David Burch

03-11-1988

(Address) _____

SUBSCRIBED AND SWORN TO before me this 8 day of March, 19 88

CONSERVATION DIVISION
 Wichita, Kansas

Notary Public

My Commission Expires: 11-13-90

