

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

AUG 1 2007

CONSERVATION DIVISION

API # 15-NA 019-19487-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1918 approx

Well Operator: QUEST Cherokee, LLC KCC License #: 33344
(Owner / Company Name) (Operator's)

Address: 211 West 14th Street City: Chanute

State: Kansas Zip Code: 66720 Contact Phone: (620) 431 - 9500

Lease: Mustoe Well #: 32A Sec. 3 Twp. 32 S. R. 12 ☒ East ☐ West

SWSE - SW Spot Location / QQQQ County: Chautauqua

701 Feet (in exact footage) From ☐ North / ☒ South (from nearest outside section corner) Line of Section (Not Lease Line)

3502 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☒ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well
☐ SWD Docket # ☐ ENHR Docket # ☐ Other:

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 8 5/8" Set at: NA Cemented with: NA Sacks

Production Casing Size: 2" Set at: APPROX 600 Cemented with: NA Sacks

List (ALL) Perforations and Bridgeplug Sets: OPEN HOLE 600-700' APPROX

Elevation: (☒ G.L. / ☐ K.B.) T.D.: 700' APPROX PBTD: Anhydrite Depth: (Stone Corral Formation)

Condition of Well: ☐ Good ☒ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): RIH AND SET BRIDGE PLUG AT BOTTOM OF CASING. PERFORATE (1 FOOT AT 4SPF) CASING EVERY 150 FOOT FROM BRIDGE PLUG TO TOP OF CASING. SQUEEZE CEMENT AND FILL CASING TO TOP. CUT OFF 2' BELOW SURFACE AND COVER

Is Well Log attached to this application as required? ☐ Yes ☒ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why? Field purchased from another party

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gary Laswell

Phone: (620) 431 - 9500 ext 244

Address: 211 West 14th Street City / State: Chanute/Kansas

Plugging Contractor: QUEST Cherokee, LLC KCC License #: 33344
(Company Name) (Contractor's)

Address: Same as above Phone: (620) 431 - 9500

Proposed Date and Hour of Plugging (if known?): TBD AFTER APPROVAL OF THIS APPLICATION

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/31/2007 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

QUEST CHEROKEE, LLC
OKLAHOMA TOWER
210 PARK AVE, STE 2750
OKLAHOMA CITY, OK 73102

May 02, 2008

Re: MUSTOE #32 A
API 15-019-19487-00-00
3-32S-12E, 701 FSL 3502 FEL
CHAUTAUQUA COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after October 29, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,



Steve Bond
Production Department Supervisor

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300