

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 007-23107-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 2-22-2007.

Well Operator: VAL Energy Inc. KCC License #: 5822
(Owner / Company Name) (Operator's)
Address: 200 W. Douglas #520 Wichita, Ks. 67202 City: _____
State: Kansas Zip Code: 67202 Contact Phone: (316) 263 - 6688
Lease: Bartholow Well #: 2-~~18~~ Sec. 18 Twp. 33 S. R. 12 East West
SW - SE - SE - _____ Spot Location / QQQQ County: Barber

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8 Set at: 311 Cemented with: 190 Sacks
Production Casing Size: 5 1/2 Set at: 4615 Cemented with: 100 Sacks
List (ALL) Perforations and Bridgeplug Sets: 4503-4520 @ 2 spft.

Elevation: 1572 (G.L. / K.B.) T.D.: 4950 P.B.T.D.: 4606 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole *Shoot casing +*
Proposed Method of Plugging (attach a separate page if additional space is needed): set CIPB, spot 2 sx cement, pull to 600 ft. pump 50 sx, pull to 311 ft. pump 50 sx. pull to 100 ft, pump 50 sx to surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? Log sent with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Russ Meyers
Phone: (316) 218 - 5853
Address: 200 W. Douglas #520 Wichita, Ks. 67202 City / State: Ks
Plugging Contractor: Clarke Corp. KCC License #: 5105
(Company Name) (Contractor's)
Address: 107 W Fowler Medicine Lodge, Ks. Phone: (620) 886 - 5665

Proposed Date and Hour of Plugging (if known?): unknown due to rig schedule

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.
Date: 4-4-2008 Authorized Operator / Agent: *Rodd Allen* (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
APR 04 2008
CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

VAL ENERGY, INC.
200 W DOUGLAS AVE STE 520
WICHITA, KS 67202-3005

May 01, 2008

Re: BARTHOLOW #2
API 15-007-23107-00-00
18-33S-12W, 330 FSL 990 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after October 28, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888