

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD 15-065-21414-00-01

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 32 TWP. 8 RGE. 25 E/W
 Location as in quarters or footage from lines:
S/2/S/2/SE

Lease Owner Geodessa Corporation c/o Sharp Eng.
 Lease Name Johnson "A" Well No. #2
 Office Address Box 8292C - Wichita, Ks. 67208
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced June 16, 1983
 Plugging completed June 21, 1983

Locate Well
 correctly on above
 Section Platt.

Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom _____ T.D. 4010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	227'	NONE
				4 1/2"	3997'	1255.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped four (4) sacks cement, sanded to 3860' and dumped four (4) sacks cement. Shot pipe @ 3000'.
 Shot pipe @ 2500', 2000', 1800', 1400' and 1200'.
 Pulled thirty-one (31) joints 4 1/2" casing.
 Squeezed well with three (3) sacks hulls, two (2) sacks gel, one hundred twenty (120) sacks cement, two (2) sacks hulls, eighteen (18) sacks gel, released plug and pumped sixty (60) sacks 50/50 pozmix cement with 6% added gel.

RECEIVED
 STATE CORPORATION COMMISSION


(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc. 7/1/83
JUL 01 1983

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1983



My Commission expires: _____

Margaret Prosser
 Notary Public.