

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-22,106 <sup>00-00</sup>

LEASE NAME Keith #1

WELL NUMBER 191' NE of NE/4 SW/4

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 34 TWP. 8s RGE. 25w (N or (W))

COUNTY Graham

Date Well Completed         

Plugging Commenced 6/14/85

Plugging Completed 6/28/85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Galloway Drilling, Inc.

ADDRESS 340 Broadway Plaza Bldg. Wichita, Ks. 67202

PHONE# (316) 263-1793 OPERATORS LICENSE NO. 5783

Character of Well         

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	259'	none
				4 1/2"	3991'	2075'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged bottom with 4 sacks cement, sand to 3700' & 4 sacks cement. Shot pipe at 2505', 2316', & 2075'. Pulled 49 joints of pipe. Plugged well with 27 gel mixed with 2 hulls, 100 cement with 1 hull, 13 gel, 8 5/8 plug, & 80 sacks 50/50 poz 6% gel, 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 19 85

Irene Hoover  
 Notary Public

My Commission Expires:         



7-5-85