


15-065-30018-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 34 Twp. 8S Rge. 25W(E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NW NW
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Setchell "A" Well No. 871
Office Address 909 Palace Bldg., Tulsa 3, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-18-65 19
Application for plugging filed 3-18-65 19
Application for plugging approved 3-18-65 19
Plugging commenced 3-18-65 19
Plugging completed 3-18-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1965

CONSERVATION DIVISION
Wichita, Kansas

3-23-65

Plug @ 540' with 20 sks. cement
Plug @ 210' with 20 sks. cement
Plug @ 40' with 1/2 sk. hulls 10 sks. cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 65



Wanda Nichols
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Herman Geo. Kaiser, Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SETCHELL A-#1
 LOCATION: NW NW NW Sec. 34-8S-25W
 GRAHAM COUNTY, KANSAS
 COMMENCED: 3-12-65
 COMPLETED: 3-18-65

0	30	Shale
30	70	Sand
70	115	Blue Shale
115	2125	Shale
2125	2190	Shale & Shells
2190	2220	Anhydrite
2220	2715	Shale & Shells
2715	2930	Shale & Lime
2930	3756	Lime & Shale
3756	4000	Lime
	<u>4000</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1965
 CONSERVATION DIVISION
 Wichita, Kansas
 3-23-65

Set 8 5/8" used surface casing @ 215' cemented with 150 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Setchell A-#1 well, located NW NW NW of Section 34, Township 8 South, Range 25 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of March, 1965.

Ulanda Nichols

Ulanda Nichols



My Commission Expires: April 1, 1967