


WELL PLUGGING RECORD

15-179-00178-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

SHERIDAN County. Sec. 1 Twp. 8 Rge. 26 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner EMPIRE DRILLING COMPANY
Lease Name DAVIS Well No. NO. 1
Office Address 400 BROWN BLDG., WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 6 1956
Application for plugging filed SEPTEMBER 6 VERBAL 1956
Application for plugging approved SEPTEMBER 10 1956
Plugging commenced SEPTEMBER 6 1956
Plugging completed SEPTEMBER 6 1956
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	179'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

BOTTOM PLUG SET AT 175' WITH 1/2 SACKS HULLS AND 15 SACKS CEMENT.
TOP PLUG SET AT 110' WITH 1/2 SACKS HULLS AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 400 BROWN BLDG., WICHITA 2, KANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD, (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
DAN J. KORNFELD
400 BROWN BLDG., WICHITA 2, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 12TH day of SEPTEMBER, 1956



Charlotte Stanley
Notary Public.

PLUGGING
FILE SEC. 1 T. 8 R. 26W
BOOK PAGE 97 LINE 26

LOG

COMPANY: EMPIRE DRILLING COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: DAVIS NO. 1

LOCATION: NE NE NE OF SEC. 1-8-26, SHERIDAN COUNTY, KANSAS

COMMENCED: AUGUST 29, 1956

COMPLETED: SEPTEMBER 6, 1956

ELEVATION: 2455 K.B.

0	TO	197	SHALE AND SAND	TOPS:		
197	TO	600	SHALE AND SHELLS			
600	TO	1306	SHALE AND SAND	HEEBNER	3637	-1183
1306	TO	2140	SHALE AND SHELLS	TORONTO	3659	-1205
2140	TO	2159	ANHYDRITE	LANSING KANSAS CITY	3675	-1221
2159	TO	2645	SHALE AND SHELLS			
2645	TO	3232	SHALE AND LIME			
3232	TO	3375	SHALE AND SHELLS			
3375	TO	3495	SHALE AND LIME			
3495	TO	3661	SHALE AND SHELLS			
3661	TO	3900	LIME			
3900			R.T.O.			

DRY AND ABANDONED

CASING: RAN 179 FT. OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.

D.S.T. #1 3690-3715 TOOL OPEN 1 HR. WEAK BLOW FOR 16 MIN. RECOVERED 35' OF MUD WITH FEW SPOTS OF OIL. 30 MIN. SHUT-IN B.H.P. 1240 LBS.

D.S.T. #2 3792-3815 TOOL OPEN 1 HR. WEAK BLOW FOR SIX MIN. RECOVERED 5' OF MUD. 20 MIN. SHUT-IN B.H.P. 0 LBS.

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE DAVIS NO. 1, NE NE NE OF SEC. 1-8-26, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY

Dan J. Kornfeld

DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 12TH DAY OF SEPTEMBER, 1956.

Charlotte Stanley

NOTARY PUBLIC

My Commission Expires June 7, 1960

PLUGGING			
FILE	SEC. 1	T. 8	R. 26w
BOOK	PAGE 97	LINE	26