

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

13-179-20004-00-00

API NUMBER 3/16/67

LEASE NAME NIBLOCK

WELL NUMBER 1

SPOT LOCATION SE SW NW

SEC. 2 TWP. 8 RGE. 26 (X) or (W)

COUNTY SHERIDAN

Date Well Completed 3/16/67

Plugging Commenced 10/22/8

Plugging Completed 10/29/8

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR JOE KATZ

ADDRESS 420 S. Dixie Highway, Suite 3B1, Coral Gables,
Florida, 33146

PHONE # (305) 661-3429 OPERATORS LICENSE NO. 6369

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas (Mr. Goodrow)

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing formation Lansing/KC Depth to top 3677 bottom 3891 T.D. 3900

PBTD 3863

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota	water	980	1250	8 5/8	207'	none
Cheyenne	"	1275	1510	5 1/2	3899'	none
Cedar Hills	"	1735	1905			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. tbq. @ 3775' Halliburton spotted 100 sx. 60/40 Poz 8% gel. 3 sx hulls: pulled tbq. to 2575' spotted 100 sx 60/40 Poz 8% gel 1 sx hulls: pulled tbq. to 1375' spotted 100 sx 60/40 Poz 8% gel & circ cement to surface: pulled tbq.: pump 3 bbls. cement & casing filled to surface: hooked to Braden head & pumped 4 bbls cement w/ 1 sx hulls & surface pipe filled up: Carl Goodrow on location & approved: cut off pipe in cellar: welded cap.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Oilwell Cementing Co. License No. _____

Address Oberlin, Kansas

STATE OF Kansas COUNTY OF Graham, ss.

Roger Welty (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Roger Welty

(Address) Box 116, Hill City, Ks.



SUBSCRIBED AND SWORN TO before me this 31st day of October, 1985

My Commission expires: May 16, 1985

RECEIVED
STATE CORPORATION COMMISSION
Laura Ann Green
12-2-85

DEC 2 1985

Form CP-4
Revised 01-84

CONSERVATION DIVISION