

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-179-20011-00-00

Sheridan County, Sec. 2 Twp. 8S Rge. 26 (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW  
Lease Owner Harry Koplin  
Lease Name Andregg Well No. 1  
Office Address 1040 Lakeshore Drive, Carlyle Apts., Chicago, Illinois  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 10 19 67  
Application for plugging filed May 10 19 67  
Application for plugging approved May 10 19 67  
Plugging commenced May 10 at 5:00 p.m. 19 67  
Plugging completed May 10 at 9:30 p.m. 19 67  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3920 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	223'	7"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 215', Halliburton plug, 15 sacks cement thru open end of drill pipe; filled hole with heavy mud to 40', Halliburton plug, 8 sacks cement and 1/4 sack hulls. 2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1967  
CONSERVATION DIVISION  
Wichita, Kansas

5-19-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
Box 129, Sterling, Kansas F. A. Wuellner, Sec.  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 19 67

My commission expires Commission Expires January 22, 1970

Bernard Laudermilk  
Bernard Laudermilk, Notary Public.



15-179-20011-00-00

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG ----- ANDREGG #1  
LOCATED: SW NW SW Section 2-8S-26W, Sheridan County, Kansas

OWNER: Harry Koplin  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 30, 1967  
COMPLETED: May 10, 1967

ROTARY TOTAL DEPTH: 3920'

LOG

0 - 170	Sand & Clay	
170 - 1120	Shale	
1120 - 2165	Sand & Shale	
2165 - 2172	Anhydrite	
2172 - 2425	Shale	
2425 - 3625	Shale & Lime	
3625 - 3692	Lime	
3692 - 3738	Lime & Shale	
3738 - 3800	Lime	
3800 - 3920	Lime & Shale	T.D.

GASING RECORD

Run 7 joints 7" OD casing, 212' pipe set at 223' K.B. with 125 sacks HA-5. Plug was down at 8:30 p.m. by Howco.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1967  
S-19-67  
CONSERVATION DIVISION  
Wichita, Kansas

Began plugging at 5:00 p.m. 5-10-67, put 15 sacks cement through open end drillpipe at 540', filled hole with heavy mud to 215', Halliburton plug. 15 sacks cement through open end drillpipe, filled on up to 40', Halliburton plug, 1/4 sack hulls and 8 sacks cement. 2 sacks cement in rathole. Job completed at 9:30 p.m.. State Plugger, Bill Nichols, Morland, Kansas.