

6 031496

API NUMBER 15- 065-17009-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C N/2 SE SW SEC. 32, T 8 S, R 24 W/4E

990 feet from S section line

3300 feet from E section line

Lease Name Holley Unit ^{KCC} Well # 10-2

County Graham

Well Total Depth 3960 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 201

TECHNICIAN'S PLUGGING REPORT

Operator License # 30420

Operator: V. J. I. Natural Resources

Name & Address 1503 Vine

Hays, Ks.

Abandoned Oil Well Gas Well Input Well xx SWD Well D&A

Other well as hereinafter indicated E - 9577 ABC

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 15 Month: Feb. Year: 19 91

Plugging proposal received from Jason Dinges

(company name) v. J. I. (phone)

were: 8 5/8 set at 201 w/150 sks. 5 1/2 set at 3960 w/150 sks. Perf at 3896 - 3919.

Shot holes at 1250 and 2100. in 5 1/2 casing. Order 50 sks common cement 250 sks.

65/35 poz 10% gel 500 lbs. hulls. Allied Cement Co. Wellbrock Water Trucks.

Elt Logging Co. Ran shot on wireline down 5 1/2 casing. Hole open.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 3:00 PM Day: 15 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 w/50 sks common cement followed w/300 sks.

cement blend w/400 lbs. hulls mixed into max psi 800 lbs. Close in psi 200 lbs.

Sq 8 5/8 w/100 sks cement blend w/100 lbs hulls to max psi 500 lbs. Close in

psi 150 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

3-13-1991
MAR 13 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 3-15-91

INV. NO. 31200

2-15

MAY 03 1991

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow