

031371

6-12

API NUMBER 15-065-02764-035

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S, R 24 W/Exx
RECEIVED JUN 28 1990
CONSERVATION DIVISION
WICHITA, KANSAS

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA Inc.

Name & Address: Box 26100

Oklahoma City, Ok. 73126-0100

Lease Name: 202 S

County: Graham 130.33

Well Total Depth: 4010' PRTD 1529 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Supply Well C.H.

Plugging Contractor: Murfin Drilling Co. License Number 6033

Address: Hill City, Ks.

Company to plug at: Hour: AM Day: 12 Month: June Year: 19 90

Plugging proposal received from: Rick

(company name) Oxy - USA (phone) _____

were: 8 5/8 set at 220 cwc w/175 sks. 5 1/2 set at 4010j w/125 sks.

pBTD 1529. Cleaned hole but to 2270. Perf 2126 anhy; holes in dakota section.

Order 400 sks 65/35 poz 6% gel. Allied Cement Co. Wellbrock Water Trucks.

Drilled out sand and 8' of cement. Plug (good plug) more sand to 2270.

Plugging Proposal Received by: Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 12 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Ran string of b.o. tubing to 2176.

Circulated cement blend to surf with backside circ from deep holes. Closed in and

sq 8 5/8 and 5 1/2. Tubing sanded in backed off top joint and left tubing in hole.

Sq 8 5/8 5 1/2 w/total of 380 sks cement blend to max psi 500 lbs.

Close in psi 500 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JUL 13 1990

Remarks: _____

(If additional description is necessary, use BACK of this CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7-24-90

INV. NO. 28727

Sub. 5

Signed: Carl Goodrow (TECHNICIAN)
Carl Goodrow