

8-23

6 031156

API NUMBER 15-065-02767-00-01  
1955

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NW SE, SEC. 33, T 8 S, R 24 W/E

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Holley LKC Well # 205W

Operator: Oxy USA Inc.

County Graham 128.86

Name & Address 3545 N.W. 58th St.

Well Total Depth 3965 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well x SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Hays, Ks.

Company to plug at: Hour: AM Day: 23 Month: August Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone) \_\_\_\_\_

were: 8 5/8" set at 224' w/NA. 5 1/2" set at 3965' w/NA. Perf anhy

at 2098' below Dakota at 1450'. Order 550 sks 60/40 Poz 8% Gel 3% Ca Cl 400# Hulls

Halliburton OWS Watertruck Murfin Rig.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1988 9/16/88

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operation attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45AM Day: 23 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 1775'. Circulated cement to surface. laid

down tubing. Tied onto 5 1/2" squeezed with total of 225 sks cement and 300# Hulls to

max psi 350#. Close in psi 200#. Squeezed annulus w/75 sks cement and 100# Hulls

to max psi 350#. Closed in Psi 150#. Plug complete.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

I ~~did not~~ observe this plugging.

DATE 9-22-88

Signed Carl Goodrow  
(TECHNICIAN)

D

INV. NO. 22377

Carl Goodrow