

031157

8-23 B2768

~~065-22768~~ 00-22

6

API NUMBER 15- 1955

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE SW, SEC. 33, T 8 S, R 24 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Holley LKC Unit Well # 206 W

Operator: Oxy USA Inc.

County Graham 131.14

Name & Address 3545 NW 58th St.

Well Total Depth 4035 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well Input Well  SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 23 Month: August Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 225' w/NA. 5' set at 4035" w/NA. Perf anhy at 2146' below Dakota at 1450'. Order 550 sks 60/40 Poz 8% Gel 400# Hulls.

Halliburton OWS Water Trucks. A full string of tubing w/packer were pulled in good condition indicating an open hole.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 12:30PM Day: 23 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/425 sks cement and 300# Hulls to max psi 350#. Close in psi 150#. Squeezed 8 5/8" w/100 sks cement and 100# Hulls to max psi 450#. Close in psi 150#. Plug complete. RECEIVED

STATE CORPORATION COMMISSION

SEP 16 1988

9/16/88

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (or my observer) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 9-22-88

INV. NO. 22376