

031158

8-23

API NUMBER 15-065-02771-00-02
1956

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE SE, SEC. 33, T 8 S, R 24 W/E

1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name: Volley LKC Unit Well # 209W

Operator: Oxy USA Inc.

County: Graham 129.09

Name & Address: 3545 N.W. 58th St.

Well Total Depth: 3972 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 150

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Halliburton License Number _____

Address: Hays, Ks.

Company to plug at: Hour: _____ Day: 23 Month: Aug. Year: 19 88

Plugging proposal received from: Pringle

(company name) Oxy IISA (phone) _____

were: 8 5/8" set at 150' w/NA. 5 1/2" set at 3998' w/NA. Perf anhy at 2140'

below Dakota at 1450'. Order 550 sks 60/40 Poz 8% Gel 400# Hulls. Halliburton OWS

Water Trucks full string of tubing and packer was pulled indication of an open hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1988

9/16/88

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00PM Day: 23 Month: August Year: 19 88

ACTUAL PLUGGING REPORT: Squeezed 5 1/2" w/420 sks cement w/300# Hulls to max psi 450#

Close in psi 250#. Squeezed 8 5/8" w/100 sks cement and 100# Hulls to max psi 300#. Close

in psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

It is recommended to observe this plugging.

DATE: 9-22-88

Signed: Carl Goodrow (TECHNICIAN)

P

INV. NO. 22375

Carl Goodrow