

10-14  
6-031597265  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 1505-02773-00-01

NE SW NE 1/4 SEC. 33, 08 S, 24 W  
3630 feet from S section line  
1650 feet from E section line

Operator license# 8790

Lease Blackburn well # 2

Operator: Kruckenberg &amp; Scott

County Graham

Address: P.O. Box 70  
Isabel, Kansas 67065

Well total depth 4011 feet 130.35  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 292 feet

Aband. oil well \_\_, Gas well \_\_, Input well X, SWD \_\_, D &amp; A \_\_

Plugging contractor: Halliburton Cement Company License# -

Address: Oberlin, Kansas

Company to plug at: Hour: P.M. Day: 14 Month: October Year: 91

Plugging proposal received from: Niel Scott

Company: Kruckenberg &amp; Scott

Phone: \_\_\_\_\_

Were: 8 5/8" set @ 292' w/250 sx. cwc. 5 1/2" set @ 4008' w/180 sx.  
PBD 3978'. Perf. 3895'-3918'. TOC 3311'. Cleaned out hole to 2250' with  
washover R.G. Bottom sanded in w/fish @ 2250'. Holes in casing from  
anhy. to 800'. Holes squeezed from 1700' to 1910'. Order 250 sx. 65/35  
poz. 10% gel. 500# hulls. Halliburton Cement Co. Cleaned out to 2250'.  
Fish wouldn't mill. Sanded in @ 2250'. Poe Well Service. LaRue  
Water Truck.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00P.M. Day: 14, Month: October, Year: 91

Actual plugging report: Ran tubing to 2165' mixed and pumped 25 sx.  
cement blend. Broke circ. Laid down 1200' of tubing. Mixed and pumped  
75 sx. cement blend to circ. cement to surface. Laid down tubing.  
Load 5 1/2", squeezed with total 150 sx. Cement blend to max. P.S.I.  
#. Close in P.S.I. #. 300# hulls blended in. Squeezed 8 5/8"  
w/100 sx. cement blend to max. P.S.I. 300#. Close in P.S.I. 150#.

2415' KB - Anhy. 2135'.

Remarks: #5 C-6453 57776-0 - #2 57775-C - In 1970 C-6453

I did [ X ] / did not [ ] observe the plugging.

INVOICED

DATE 11-22-91

INV. NO. 33829

(agent)

Form CP-2/3

10-14 JAN 28 1992