

1-10

427 R

6 - 031645

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-045-19099-00-00
1955

SWNE /4 SEC. 33, 08 S, 24 W
4290 feet from S section line
990 feet from E section line

Operator license# 8790 Lease Blackburn well # 3

Operator: Krukenberg & Scott County Graham

Address: Box 70 Well total depth 4025 feet
Isabel, Ks. 67065 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ 314 feet

130.81

Aband. oil well xx, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License#

Address: Chase, Ks.

Company to plug at: Hour: AM Day: 10 Month: Jan. Year: 92

Plugging proposal received from: Vernon

Company: Kelso phone:

Were: Order sand and common cement. Pull pipe. Order 225 sks
65/35 poz 10% gel. 500 lbs hulls. Allied Cement Co. Shots at anhy 1800.
base dk. 1400. Hole open to perms w/bailer.

STATE RECEIVED
CORPORATION COMMISSION
2/14/92
FEB 14 1992
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:30AM, Day: 10, Month: Jan.

Actual plugging report: 8 5/8 at 314 w/250 sks. 5 1/2 at 4025
w/150 sks. Plugged bottom w/sand and 5 sks cement to 3910. Shot pipe
4 times and rec 1000. Pump in 5 1/2. Sand back to 3975 w/5 sks cement.
Shot off pipe. Pumped cement blend to 1800. Laid down 5 1/2 casing.
Squeezed 8 5/8 w/cement blend.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: , NO
Plugged through TUBING , CASING Elevation: 2425 GL

INVOICED

DATE 2-17-92 did / did not observe the plugging.

WELL NO 34577

Carl Goodrow
Carl Goodrow (agent)
Form CP-2/3