

To: <sup>6030540</sup>  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-22,165 <sup>00-00</sup>

NEESEC. 35, T B, S, R 24

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name KEITH Well # 1

Operator: THUNDERBIRD DRUG. INC.

County GRAHAM 129.35

Name & Address P.O. Box 18407

Well Total Depth 3980 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67218

Surface Casing: Size 8 5/8 feet 250'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor THUNDERBIRD DRUG. INC. License Number 5131 #38

Address AS ABOVE

Company to plug at: Hour: AM Day: 6 Month: 8 Year: 19 85

Plugging proposal received from ED COOKE

(company name) THUNDERBIRD DRUG. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 250' WITH HOLE FULL OF NO LESS THAN 36 VLS. MUD  
NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE  
ORDER 190 SX. 60/40 PZ 6% GEL. 3% C. 8 5/8 W.P.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30AM Day: 6 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ ANHY BREAK CIRC. DISPLACE 25 SX. CMT.  
MIX. LAYDOWN D.P. TO 1200' DISPLACE 100 SX. CMT MIX. + 1 SX. FLO SEAL  
LAYDOWN D.P. TO 250' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P.  
PUSH W.P. TO KELLY DEPTH FILL HOLE FROM W.P. TO BASE OF  
CELLAR W/10 SX. CMT. MIX. DISPLACE 15 SX. CMT. MIX. IN RATHOLE  
W/JOINT OF PIPE. PLUG COMPLETE

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did ( ) observe this plugging.

DATE 9-6-85

INV. NO. 9904

Signed Carl Goodrow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 3 1985  
CONSERVATION DIVISION  
Wichita, Kansas