

4-031960

8-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,744-0000
70' E. of
SE NW NW /4 SEC. 36, 08 S, 24 W
4290 feet from S section line
4220 feet from E section line

Operator license# 9482 Lease Gates well # 2

Operator: National Petroleum Reserves, Inc. County Graham

Address: 250 N. Rock Road Well total depth 3990 feet
Suite #340 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67206 Surface pipe 8 5/8 Inch @ 213 feet

129.68

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 8 Month: August Year: 94

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone:

Were: Order 190 sxs. 60/40 pozmix - 8% gel.
Halliburton.
Condition hole with 36 vis. mud or better.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 7:00A.M., Day: 8, Month: August, Year: 94

Actual plugging report: Spot plugs with drill pipe.
1st. plug @ 2090' w/25 sxs.
2nd. plug @ 1250' w/100 sxs.
3rd. plug @ 260' w/40 sxs.
4th. plug @ 40' w/10 sxs.
Circulated 15 sxs. in rathole.

STATE CORPORATION COMMISSION

AUG 12 1994

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Anhy. 2085' - 2120'.

8-12-94

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: 2402 GL

I did [], did not [X] observe the plugging.

Carl Goodrow

DATE 8-26-94

100

(agent)

INV. NO. 41028