

15-005-01347-00-01

R

6 030371

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
NWSE NW SEC. B, T B S, R 25 W/E  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: BEREN CORPORATION  
Name & Address 970 4TH. FINANCIAL CENTER  
WICHITA, KANSAS  
67202

Lease Name H.E. MADDEN Well # 3  
County GRAHAM 128.54  
Well Total Depth 3955 feet  
Conductor Pipe: Size \_\_\_\_\_ feet ✓  
Surface Casing: Size 8 5/8 feet 1364' 4750ft.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050

Address Box 347 CHASE KANSAS 67524

Company to plug at: Hour: AM Day: 19 Month: 12 Year: 19 84

Plugging proposal received from MILLARD KELSO

(company name) KELSO CASING PULLING (phone) \_\_\_\_\_

were: 5 1/2 sat @ 3953' w/ 200ft PBD 3937 PERFS @ 3906-10', 3924-29' Bottom plug w/ bailer 4sr.  
Com. Com. Washdown sand to 3800' w/ bailer 4sr com. com. on sand. Shot off Pull pipe. Rec. 2527' w/ sh  
Order: 170 gal 50/50 pg 6 1/2 gal 3 1/2 cc - 40 ex gal - 400' Hulls - 1-8' Kuriper plug for top Plug.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45AM Day: 19 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Bottom Plug 4sr on bottom w/ bailer sand to 3800' - 4sr com w/ bailer  
Top Plug - Pump down 8 5/8" w/ 400' Hulls mixed w/ 22 gal - 100 ex com. mix - 18 ex gal - 8 5/8" plug  
70 ex com. mix to bottom of collar. 100 ex com across Dakota 70 ex on top to cover  
fresh water. Max press = 600# shut in 150#

RECEIVED  
STATE CORPORATION COMMISSION  
1-7-85  
JAN 07 1985

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this report)

INVOICED  
and not observe this plugging.

DATE 1-14-85  
INV. NO. 6400

Signed Carl Goodrow  
(TECHNICIAN)

Jan 14-85  
mjh  
3