

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21250-00-00
Spot: CSENWSW Sec/Twnshp/Rge: 8-8S-25W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: DAVIS Well Number: 1
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

Conductor Pipe: Size feet: 3 130.65
Surface Casing: Size 8.625 feet: 285 w/225 sxs cmt
Production: Size 4.5 feet: 3991
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/22/2001 9:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/22/2001 10:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 285' w/225 sxs cmt. 4 1/2" set at 3991'.
D.V. Tool at 2187' cwc but dropped.
Prod. Perfs 3917' - 3939'.
Shot off and recovered 750' of 4 1/2" casing.
Mixed and pumped 125 sxs cement blend with 500# hulls to Max. P.S.I. 100#. Held.
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

RECEIVED

OCT 30 2001

KCC WICHITA

INVOICED

DATE 10-30-01

INV. NO. 2002060880

OCT 25 2001

K&E PETROLEUM INC
 816 UNION CENTER #1 DAVIS
 WICHITA, KS 67202
 CONTR ABERCROMBIE DRILLING CTY GRAHAM

REC'D
 8-8-25
 SE NW SW
 OGI 25
 KCC MICHIGAN

GEOL _____ FIELD SCHMIED NW EXT (1/4 S)

E 2475 KB CM 6/18/80 CARD ISSUED 8/21/80 IP P 93.3 BOPD &

API 15-065-21,250

NO WTR
 LANS 3917-3939 1/2 OA

+	+	+
+	+	+
+	+	+

LOG TOPS	DEPTH	DATUM
ANH	2170	+ 305
TOP	3496	-1021
HEEB	3710	-1235
TOR	3732	-1257
LANS	3746	-1271
G KC	3966	-1491
LTD	4021	-1546
RTD	4020	-1545

8-5/8" 285/225sx, 4 1/2" 3991.27, DV
 TOOL 2187.45

DST (1) 3765-3805/45-45-45-45, REC
 20' M W/SPKS 0, SIP 793-741#, FP
 21-42/42-52#

DST (2) 3807-3845/30-45-30-60, REC
 109' GIP, 15' HO&GCM, (20% OIL),
 124' O&GCM, 62' SL OCM, 62" M,
 SIP 481-460#, FP 21-84/105-136#

DST (3) 3862-3908/45-45-45-45, REC
 10' SL O&GCM, 62' M W/SL SO, SIP
 876-751#, FP 42-52/52-63#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)