

4-041962

4-20

API Number: 15-065-02850-00-00
1954

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

RECEIVED
KANSAS CORP COM
1998 APR 30 A 11:19
4/30/98

NE SW SW /4 SEC. 16, 08 S, 25 W
990 feet from S section line
990 feet from W section line

Operator license# 5669

Lease: Madden Davis Well # A-3

Operator: Helberg Oil Company

County: Graham 123.73

Address: P.O. Box 32
Morland, Kansas 67650

Well total depth 3807 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 200 Feet
W/115 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 20 Month: April Year 1998

Plugging proposal received from: Jerry Helberg

Company: Helberg Oil Company Phone: -

Were: 5 1/2" casing set at 3797' w/100 sxs cement. Perfs at 3658' - 3798'.
Anhy at 2054' - Dakota at 1200'.
Ordered 225 sxs 60/40 pozmix - 10% gel plus 17 sxs gel plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:30 P.M., Day: 20, Month: April, Year: 1998

Actual plugging report: R.I.H. with perf. Shot casing at 2054' and 1200'. Rigged up
cementers to 5 1/2" casing. Pumped 200 sxs cement with 400# hulls. Max. P.S.I. 300#.
8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 200#.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis J. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 5-5-98
INV. NO. 50438