

4-041963

4-20

4/30/98

API Number: 15 ⁰⁶⁵⁻⁰²⁸⁵¹⁻⁰⁰⁻⁰⁰ 1954

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

RECEIVED
KANSAS CORP
1998 APR 30 A 11:19
SW NW SW /4 SEC. 16, 08 S, 25 W
1650.0 feet from S section line
330 feet from W section line

Operator license# 5669

Lease: Madden Davis A Well # A-4

Operator: Helberg Oil Company

County: Graham 123.83

Address: P.O. Box 32
Morland, Kansas 67650

Well total depth 3810 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 156 Feet
W/110 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 20 Month: April Year: 1998

Plugging proposal received from: Jerry Helberg

Company: Helberg Oil Company Phone: 785-627-5665

Were: 5 1/2" casing set at 3798' w/75 sxs cement. Perfs at 3670' - 3735'.
Anhy at 2060' - Dakota at 1200'.
Ordered 225 sxs 60/40 pozmix - 10% gel plus 17 sxs gel plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 20, Month: April, Year: 1998

Actual plugging report: R.I.H. with perf. Shot casing at 2060' and 1200'. Rigged up cementers to 5 1/2" casing. 25 sxs with 200# hulls, followed with 17 sxs gel, followed with 175 sxs cement with 200# hulls. Max. P.S.I. 700#. S.I.P. 500#. 8 5/8" S.P. Squeezed 25 sxs with 100# hulls. Max. P.S.I. 100#. S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC X, NO
Plugged through TUBING CASING X
Anhy.plugin: YES X NO
Dakota plug: YES X, NO
Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis T. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 5-5-98

INV. NO. 50439