

6 030673 | S-065-02788-00-01

35-127
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15~~ 9-22-54

NEW NE. SEC. 17, T. B, S, R 25 (W)

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name MADDEN-DAVIS Well # 105

Operator: PETROLEUM MNG. INC.

County GRAHAM 127.04

Name & Address 400 N. WOODLAWN STE. 201

Well Total Depth 3909 POTO 3880 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67208

Surface Casing: Size 10 3/4 feet 486'

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CMT CO. License Number _____

Address PLAINVILLE & RUSSELL KANSAS.

Company to plug at: Hour: PM Day: 20 Month: 2 Year: 19 86

Plugging proposal received from WAYNE FUZZELL

(company name) P.M.I. (phone) _____

were: 10 3/4 @ 486' w/230sx. 7" @ 3903 w/100sx. PERF 3718-3821

ORDER 250sx. 60/40 P02 6 GEL 3% ALL 35 SX. GEL 5sx. HULLS

ALLIED CMT. CO. KEITH WATER.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 PM Day: 20 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT MIX. & PUMP DOWN 7" 5sx. HULLS + 50sx. CMT MIX.

35sx. GEL 150sx. CMT. MIX. MAX. PSI 500* CLOSE IN 150*

MIX. & PUMP DOWN BACKSIDE 50sx. CMT. MIX. MAX. PSI 300* CLOSE IN 150*

PLUG. COMPLETE

Remarks: (If additional description is necessary, use BACK of this form.)

I did (not) observe the STATE PLUGGING COMMISSION

RECEIVED

DATE FEB 28 1986

FEB 28 1986

Signed Carl Goodrow (TECHNICIAN)

16
2-28-86

INV. NO. 12774-2-20

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84