



15-179-20098-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 28 1968
 CONSERVATION DIVISION
 Wichita, Kansas

5-28-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Koster Well No. 1

Location: CSE-SE Sec. 29 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4140 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

230'--8 5/8" Surface pipe, cement circulated with 210 Sx.
Top of Dakota section @ 1225'.

Circulate hole with heavy mud. Pull DP to 1450' and displace 100 Sx
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent