



15-179-20203-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

300 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
5-6-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company and Adair Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Koster Well No. 1

Location: SW-NW-SW Sec. 29 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4170 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

2491-- 7" O D Surface casing, cement circulated with 80 Sx. (6 1/4" Hole).  
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 65 Sx.  
cement thru DP. Pull DP to 275' and displace 15 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent