



15-179-20316-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION  
Wichita, Kansas

7-3-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Geerdes <sup>KCC</sup> A <sup>LAP</sup> Well No. A-1

Location: CNW-SE Sec. 30 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 2548' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shawn was instructed to plug the well as follows:

263'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 110 Cu. Ft. cement thru DP from 1525' to 1200'. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP from 275' to 200'. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent