



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
09-15-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20265-00-00

Dear Sir:

Mr. Ed. Weiler of Shields Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Ibson Well No. 1

Location: NE-NE-NW Sec. 14 Twp. 8 Rge. (E)(W) 30

County: Sheridan Total Depth 4298' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Weiler was instructed to plug the well as follows:

290'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 100 Sx.  
cement thru DP. Pull DP to 325' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent