



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1972
06-28-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20315-00-00

Dear Sir:

Mr. Virgil Shawn of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Shawn guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Howard Well No. 1

Location: SE-SE-NE Sec. 26 Twp. 8 Rge. (E)(W) 30

County: Sheridan Total Depth 4205' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Shawn was instructed to plug the well as follows:

266'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent