



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

09-20-1968

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 20 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-179-20132-00-00

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: McCormick Well No. 1

Location: CSW-NW Sec. 35 Twp. 8 Rge. (E)(W) 30

County: Sheridan Total Depth 4250' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

278'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1425'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 100 Sx.  
cement thru DP. Pull DP to 305' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent