



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

15-193-20013-00-00

02-19-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. Inc. has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Christenson <sup>KCC</sup> Christensen <sup>ZAP</sup> Well No. 1

Location: NE-NE-NE Sec. 34 Twp. 8 Rge. (E)(W) 31

County: Thomas Total Depth 4645' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 275 Sx.  
4613'--5 1/2" Production casing cemented on bottom with 150 Sx. Well  
plugged back to 4050'. Top perforations @ 4020'.

Sand well back to 4000' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 5 sacks hulls, 35 sacks gel and 135 Sx.  
cement, staged.

Very truly yours,

Conservation Division Agent