



15-193-20028-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1970

CONSERVATION DIVISION
Wichita, Kansas

3-23-70

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Ryan Well No. E-1

Location: 145' So. of CNE-SW Sec. 27 Twp. 8 Rge. (E)(W) 32

County: Thomas Total Depth 4690' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

452'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1625'.

Circulate hole with heavy mud. Pull DP to 1850' and displace 100 Sx.
cement thru DP. Pull DP to 465' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. J. Nichols
Conservation Division Agent