



15-193-20004-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

7-15-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Younger Well No. A-1

Location: CSW-NW Sec. 7 Twp. 8 Rge. (E)(W) 35

County: Thomas Total Depth 3250' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

249'--8 5/8" Surface pipe, cement circulated with 190 Sx.
Top of Dakota section @ 1630.

Circulate hole with heavy mud. Pull DP to 1860' and displace 100 Sx.
cement thru DP from 1860' to 1540'. Pull DP to 275' and displace 20 Sx.
cement thru DP from 275' to 215'. Pull DP, set bridge @ 40' with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent