



15-193-20014-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1969
CONSERVATION DIVISION
Wichita, Kansas

4-29-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Garvey Well No. A-1

Location: CSE-SW Sec. 7 Twp. 8 Rge. (E)(W) 35

County: Thomas Total Depth 4930 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

2 1/8" - 8 5/8" surface casing, cement circulated with 270 Sx.
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1920' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent