



15-193-20021-00-00.

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

8-6-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Murfin-Nadel & Gussman,

Complete Address: 617 Union center building, Wichita, Kansas.

Lease Name: Dawes Well No. 1

Location: CNW-SW Sec. 31 Twp. 8 Rge. (E)(W) 35

County: Thomas Total Depth 5050 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

268'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Dakota section top @ 1650'.

Circulate hole with heavy mud. Pull DP to 1875' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent