



15-193-20019-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin-Nadel & Gussman,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Guise Well No. 1

Location: SW-SW-NW Sec. 18 Twp. 8 Rge. (E)(W) 36

County: Thomas Total Depth 4985' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

311'---8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1750'.

Circulate hole with heavy mud. Pull DP to 1975' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent