

4-032389

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,087-0000

SE NE SE /4 SEC. 34 , 08 , 29 W
1650 feet from S section line
330 feet from E section line

Operator license# 5552

West Hoxie Unit
Lease: Currier Well # 1

Operator: Gore Oil Company

County: Sheridan

Address: P.O. Box 2757
Wichita, Kansas 67201-2757

Well total depth 4225 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 224 feet

Aband. oil well X , Gas well , Input well , SWD , D & A

Plugging contractor: Express Well Service, Inc. License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: A.M. Day: 5 Month: October Year: 1999

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order work string.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:00 A.M. , Day: 5 Month: October , Year: 1999

Actual plugging report: 8 5/8" set at 224' w/190 sxs cwc. 4 1/2" set at 4224' w/200 sxs.
Prod. Perfs 4093' - 4096'. Casing hole at 2300'. P.B.T.D 4190'. Left packer, 2 joints tubing
and 4 rods and pump in bottom of hole. Ran work string to 3200'. Mixed and pumped 200 sxs
cement blend with 500# hulls mixed in through tubing to circulate cement. Squeezed 8-5/8"
with 100 sxs cement blend to Max. P.S.I. 300#. S.I.P. 300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X , NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 20 1999

CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-26-99
INV. NO. 60740

10/20/99

A