

6-100504

10-22

00-00

TO:

API number: 15-193-20638

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE SE /4 SEC. 30, 08 S, 32 W  
1650 feet from S section line  
990 feet from E section line

Operator license# 4197

Lease McCartney well # 1-30

Operator: Dunne Oil Company

County Thomas

152.59

Address: 100 South Main  
Suite 410  
Wichita Ks. 67202

Well total depth 4695 feet  
Conductor Pipe: inch @ feet  
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: White & Ellis Drilling License# 5420

Address:

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Judy (secretary)

Company: White & Elis Drilling phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2730 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1925 feet " 100 " Mousehole: sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " Wiper plug & 10 sx.

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 12:30 pm, Day: 22, Month: October, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1995

Remarks: Elevation: 3128 GL, Anhydrite depth: 2727 - 2754 feet, Anhy. plug: YES

Dakota plug: YES Bottom hole plug in place: NO

Plugged through drill pipe: YES

Did NOT penetrate Arbuckle, cemented by Allied Cementing

11-13-95

I did [ ] did not [ X ] observe the plugging.

David K. Wann P.I.R.T. II  
(agent)

HD

Form CP-2/3

INVOICED

DATE 11-14-95

INV. NO. 44011