

4 060051

1-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-193-20,494-00-00

NW SW NE, SEC. 34, T 8 S, R 32 W/E  
3630 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5558

Lease Name Bastin Well # 1

Operator: Dawson-Markwell Exploration, Co.  
Name & Address: 3620 N.W. 58th Street  
Oklahoma City, OK 73112

County Thomas 151.35

Well Total Depth 4657 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling Co. License Number 5420

Address Wichita, KS

Company to plug at: Hour: 5:00PM Day: 17 Month: January Year: 1990

Plugging proposal received from Don Demel

(company name) White & Ellis Drilling Co. (phone) 316-263-1102

were: Space all plugs through drill pipe with heavy drilling mud.

Order 190 sxs, 60/40 pos 6% gel w/ floccel per sx.

After orders were received the logging company-Great Guns- lost a neutron source due to problems with stuck tool and cut line. Neutron source was driven to bottom of well and the hole logged to determine if there were any source leaks and to confirm location of tool.\*\*

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXXXX

Operations Completed: Hour: 5:00PM Day: 17 Month: January Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 4655' with 100 sxs. with 3 gal. red paint

Note: Plugging plan was 2nd plug at 2700' with 25 sxs. Anhydrite 2688-2708'

changed without contact 3rd plug at 1875' with 100 sxs. Dakota 1576-1876'

with Dist #4 office 4th plug at 410' with 40 sxs. Surface pipe to 358'

5th plug at 40' with 10 sxs. wiper plug at 40'

pathole 15 sxs., Brass plate welded to top of well.

Remarks: Halliburton Cementing. Gunk in hole to prevent OWWO

(If additional description is necessary, use BACK of this form.)

XXXX / did not) observe this

\*\*See attached documents from Great Guns. Signed Herb Deines (TECHNICIAN)

None of the five entities involved notified the KCC office until after the well was plugged. Herb Deines

INVOICED

DATE 2-15-90

INV. NO. 27452

RECEIVED CONSERVATION DIVISION WICHITA, KANSAS FEB 14 1990

2-14-90