

4-070151

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-4

API Number: 15-193-20,670-0000-00-00

S2 SW SE /4 SEC. 14, 08 S, 33 W
330 feet from S section line
1980 feet from E section line

Operator license# 6484

Lease: Bremenkamp Farms Well # A-1

Operator: Anderson Energy, Inc.

County: Thomas 152.75

Address: 1305 E. Waterman - Suite A
Wichita, Kansas 67211

Well total depth 4700 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 302 feet
W/200 sxs.

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Shields Drilling Company, Inc. License# 5184

Address: Shields Building - 326 Main - P.O. Box 709 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 4 Month: August Year: 1999

Plugging proposal received from: Bert Berry

Company: Shield Drilling Company, Inc. Phone: 785-483-3141

Were: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4 Floseal per sack. One 8 5/8" wiper plug.
Spot plugs through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 6:00 P.M. Day: 4, Month: August, Year: 1999

Actual plugging report: No arbuckle cut.

1st Plug 2732' w/25 sxs. Middle of Anhy.

2nd Plug 1810' w/100 sxs. Dakota Base +300'. RECEIVED

3rd Plug 352' w/40 sxs. Base Surface pipe +50'. STATE CORPORATION COMMISSION

4th Plug at 40' w/10 sxs. One 8 5/8" wiper plug. AUG 11 1999

Rathole w/15 sxs.

Mousehole with 10 sxs.

CONSERVATION DIVISION

Wichita, Kansas 8-11-99

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING Elevation: 3110 GL

I did [] / did not [X] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 8-20-99

INV. NO. 60296

(R)