

6 030798

API NUMBER 15-193-20, 186-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C. NW, SEC. 25, T. 8 S, R. 33 (W)

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4569

Lease Name VACIN FARMS Well # 1

Operator: Jay Boy Oil, Inc.

County THOMAS 156.10

Name & Address 8400 KILLARNEY

Well Total Depth 4803' feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67206

Surface Casing: Size 8 5/8 feet 610'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor POE WELL SERVICE License Number 6779

Address Box 115 OBERLIN KANSAS 67749

Company to plug at: Hour: PM Day: 14 Month: 10 Year: 19 86

Plugging proposal received from EDDIE POE

(company name) POE WELL SERVICE (phone) \_\_\_\_\_

were: 8 5/8 @ 610' CWC 4 1/2 @ 4799' w/ 188 SX. PBTD 4762' PERF. 4716'-20'

ORDER SAND & COM. CMT. SHOTS & PULL PIPE - ORDER 200 SX. ECANOLITE

65/35 P02 10 P02 2 DICEL. 5 SX. HULLS ALLIED CMT. CO. JOE NEUMAN

WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 PM Day: 14 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD 4762' TO 4660' SPOT 4 SX. COM.

CMT. ON SAND w/ BAILER. SHOT & PULLED 1760' OF 4 1/2" CSG.

TIE ON TO 8 5/8" CSG. MIX. & PUMP 10 bbl CMT. SKURRY - 4 SX. HULLS - <sup>180</sup> 180 SX

CMT. MIX. + 1 SX. HULLS. (200 SX. CMT. MIX. TOTAL) TO PRESSURE MAX.

PSI 250# CLOSE IN 250# Plug COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-24-86

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 15240  
10-14

NOV 14 1986

10-24-86