

6 030799
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20,403 -00-00
SWSW SE. SEC. 34, T 8 S, R 33 W1
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4569
Operator: JAY BOY OIL, INC.
Name & Address 8400 KILLARNEY
WICHITA, KANSAS
67206

Lease Name H & H FARMS Well # 1
County THOMAS 185.90
Well Total Depth 5720 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor POE WELL SERVICE License Number 6779

Address Box 115 OBERLIN KANSAS 67749

Company to plug at: Hour: AM Day: 14 Month: 10 Year: 19 86

Plugging proposal received from EDDIE POE

(company name) POE WELL SERVICE (phone) _____

were: 8 5/8 SET @ 261' W/185 SX. 4 1/2 SET @ 505' W/250 SX. SECOND STAGE 450 SX.

THIRD STAGE 300 SX. CEMENT TO 960' PBTD 5028' PERF. 4930'-35'

ORDER SAND & COM. CMT. SHOOT & PULL PIPE. - ORDER 200 SX. ECONOLITE

65/3502 10% GEIR 2 DICEL (AT) ALLIED CMT. CO. JOE NEUMAN WATER TRUCKS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 AM Day: 14 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD 5028' TO 4880' SPOT 4 SX. COM.

CMT. ON SAND W/BAILER. 2 SHOTS @ 960' AND 860' RECOVERED 860' OF 4 1/2 CGS

TIE ON TO 8 5/8" CGS. MIX. & PUMP 10 bbl CMT. SLURRY (20 SX. CMT. MIX.)

5 SX. HULLS (12 bbl) - 90 bbl CMT. MIX SLURRY (180 SX.) TO PRESSURE

MAX. PST. 400# CLOSE IN 150# PLUG COMPLETE

Remarks: _____
(If additional description of work is necessary, use BACK of this form.)

INVOICED

DATE 10-24-86

INV. NO. 15239

NOV 14 1986

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

10-24-86

OCT 24 1986

Signed Carl Goodrow
(TECHNICIAN)

10-24-86