

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-181-20057-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 13-8S-39W  
330 feet from S Section Line, 2970 feet from W Section Line  
Lease/Unit Name: WRIGHT Well Number: 1-13  
County: SHERMAN Total Vertical Depth: 1027 feet

Operator License No.: 30282  
Op Name: LOBO PRODUCTION, INC  
Address: 6715 ROAD 22  
GOODLAND, KS 67735

Conductor Pipe: Size feet: \$35.00  
Surface Casing: Size 5.5 feet: 324  
Production: Size 2.875 feet: 1027  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/29/2003 2:15 PM  
Plug Co. License No.: 30282 Plug Co. Name: LOBO PRODUCTION, INC  
Proposal Rcvd. from: JOHN SANDERS Company: LOBO PRODUCTION, INC Phone: (785) 899-5684

Proposed Plugging Method: Ordered 100 sxs 60/40 pozmix - 10% gel - 100# hulls.  
Plug thru casing.  
Pump 50 sxs between 2 7/8" and 5 1/2" casing.

RECEIVED  
2-5-03  
FEB 05 2003

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 01/29/2003 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforations 916' - 952'.  
TD 1027'.  
Connected to 5 1/2" surface pipe - pumped 40 sxs cement and 50# hulls.  
Max. P.S.I. 800#. S.I.P. 150#.  
Connected to 2 7/8" production casing - pumped 25 sxs cement with 50# hulls.  
Max. P.S.I. 1200#. S.I.P. 150#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman PART 1

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 2-5-03

NO. 2003061167

JAN 31 2003

IMAGED

BENSON MINERAL GROUP, INC  
 3200 ANACONDA TOWER #1-13 WRIGHT 13-8-39W  
 555 17TH ST, DENVER, CO 80202 SW SW SE  
 CONTR B & N DRLG. CO. CTY SHERMAN

GEOL \_\_\_\_\_ FIELD GOODLAND NIOB GAS AREA

E 3605 GL CM 7/27/79 CARD ISSUED 11/15/79 IP SIGW  
 NIOB 916-52

+	+	+
+	+	+
+	+	+

API 15-181-20,057

LOG	TOPS	DEPTH	DATUM
NIOB NOT	RELEASED		
RTD	1028	+2577	

5 1/2" 324, 2-7/8" 1027

NO DST'S  
 MICT - CO, PF (NIOB) 916-52, FRAC  
 20,000 G FOAM & 44,000#SD - SIGW -  
 POTENTIAL NA

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS