

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20352-00-00
Spot: W2SESE Sec/Twnshp/Rge: 19-9S-12W
630 feet from S Section Line, 940 feet from E Section Line
Lease/Unit Name: REXROAT Well Number: 1-19
County: OSBORNE Total Vertical Depth: 3565 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 212 150 SX CMT
Production: Size 4.5 feet: 3558 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/03/2002 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: QUALITY WELL SERVICE, INC. Phone: (620) 793-0915

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/03/2002 4:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3142' and dumped 4 sxs cement.
Shot off casing at 1533'. Pulled to 1500'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 1075' and pumped 40 sxs cement with 100# hulls.
Pulled to 650' and pumped 30 sxs cement.
Pulled to 200' and circulated with 40 sxs cement.

RECEIVED
DEC 13 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MM

Signed

Case Morris

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-13-02

INV. NO. 2003060946

DEC 11 2002

F G HOLL COMPANY LLC
WICHITA KS 67278-0167

WILDCAT

19-09S-12W
630' FSL & 940' FEL, SEC

#1-19 REXROAT

site: 12-1/4 S OF OSBORNE KS	cty: OSBORNE	API 15-141-20352
contr: STERLING DRILLING #1	field: WC (WINFIELD TWSP DISC)	
gest:		
fr date 11/14/2001	spdr date 11/27/2001	drig comp 12/07/2001
		card issued 08/12/2002
		last revised 08/12/2002

ELV: 1909 EGL
tops.....depth/datum
RTD.....3565 -1656
NO TOPS RPTD

IP status:
OIL, LKC, INTV NA , 03/01/2002
CSG: 8-5/8" 212 / 150 SX (ALT 2), PROD CSG NA
NO CORES
4 DSTS TAKEN - DETAILS NA
TRGT ZN: LKC (OIL), PTD 3200 (LKC), MICT - CO, PF (LKC)
INTV NA, GSO, POP, OIL WELL (POTENTIAL NOT RPTD),
3/1/2002 - TIGHT HOLE - NO OTHER INFO AVAILABLE -
TEMP COMP 8/12/2002

COPYRIGHT 2002
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS