

4-032092

7-16

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-141-20,299 00-00

SE SE SE / 4 SEC. 28, 09S, 12 W  
330 feet from S section line  
330 feet from E section line

Operator license# 3345 Lease: Scott Well # 1  
Operator: Leroy E. Tobias County: Osborne 108.06  
Address: HC 69 - Box 42 Well total depth 3325 feet  
Bunker Hill, Kansas 67626 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 216 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Shields Drilling Company License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 16 Month: July Year: 1995

Plugging proposal received from: Burton Beery

Company: Shields Drilling Company Phone: -

Were: Order 190 sxs 60/40 pozmix - 6% gel - 3% c.c.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 2:45 A.M., Day: 16, Month: July, Year: 1995

Actual plugging report: 8 5/8" set at 216' w/140 sxs cwc.

Spot cement plugs with drill pipe.

1st. Plug at 850' w/25 sxs.

2nd. Plug at 660' w/90 sxs.

3rd. Plug at 260' w/40 sxs.

4th. Plug at 40' w/10 sxs. - W.P.

Circulated 15 sxs in rathole - circulated 10 sxs in mousehole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1995

CONSERVATION DIVISION  
Wichita, Kansas

925-95

Remarks:

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES 850 NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did[ ] did not[ X ] observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

INVOICED  
DATE 10-3-95  
INV. NO. 43629

HO.