

4-060808

-00-013

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-27

API Number: 15-141-20,234

NW NW NW /4 SEC. 29, 09 S, 12 W
4950 feet from S section line
4950 feet from E section line

Operator license# 31574

Lease: Kendig Well # 1

Operator: Barline Oil Company

County: Osborne

Address: 106 W. Main
Osborne, Kansas 67473

Well total depth 3350 108.88 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 842 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67524

Company to plug at: Hour: A.M. Day: 27 Month: December Year: 1995

Plugging proposal received from: Kent Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-537-3361

Were: Order 165 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.
Well testing non-commercial.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 12:00 P.M., Day: 27, Month: December, Year: 1995

Actual plugging report: 8 5/8" to 842' with 365 sxs. 4 1/2" to 3343' with 130 sxs. Perfs at 3235' - 3239' with CIBP at 3230' and 3206' - 3212'. Sanded to 3150' and spotted 4 sxs cement with dump bailer. Cut casing at 2903' and pulled to 1075'. Mixed and pumped 50 sxs cement with 300# hulls. Pulled casing to 500' and circulated cement with 100 sxs. Pulled casing with cement cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 12 1996

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: 1929 GL

If did/did not [X] observe the plugging.

[Signature] (agent)

Form CP-2/3

INVOICED

DATE JAN 12 1996

INV. NO. 44544

1-8-96