

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20, 174-00-00

NE-SE-NW Sec. 27, T 9 S, R 15 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name SCHULTZE Well # 5-27

Operator: GRAHAM-MICHAELIS
Name & Address: P.O. BOX 147 CORP.
WICHITA, KANSAS
67201

County OSBORNE

Well Total Depth 3650 feet \$118.63

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor REVLIN DRLLG License Number 5671

Address P.O. BOX 293 RUSSELL, KANSAS 67665

Company to plug at: Hour: 9:15 AM Day: 16th Month: JUNE Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO STAN LINGREEN

(company name) REVLIN DRLLG (phone) 913-483-5355

were: 8 5/8" - 284' SB. CUM 1/80" COMMON QUICK SET (BY ALLIED)
ORDER 160 50/50 PORMIX 4% GEL - 3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
NO ARBUCKLE, ELV. 2018, HNH. 1239.

Signed *Michaelis*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:15 AM Day: 16th Month: JUNE Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 160 50/50 PORMIX 4% GEL - 3% CA-CL. AND 8 5/8" PLUG
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1st Plug @ 1260 FT 1/20" CNT, 2nd Plug @ 840 FT 1/80" CNT
3rd Plug @ 300 FT 1/40" CNT. 4th Plug SOLID BRIDGE 40 FT 1/10" CNT.
10th IN RAT HOLE, (CIRCULATE) (CEMENTED BY ALLIED)

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1983
6-17-1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as here stated
and that I (did / did not) observe this plugging.

Signed *Michaelis*
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 6-24-83
INV. NO. 4654-W