

15-141-20, 116-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15

SW, Sec. 31, T 9 S, R 15 WE

340 feet from N(S) section line

1020 feet from (W)E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Horkmeister Well # 2-13

Operator: Graham-Michael's Corporation
Name & Address 211 N. Broadway, Box 247,
Wichita, Ks. 67202

County Osborne

Well Total Depth 3640 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 254

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Ks. 67524

Company to plug at: Hour: 9:30 AM Day: 20 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Bob Branaman

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order out 165 sacks 50 premix-4 3/4" seal-3 3/4" lat. cl., 5 sacks balls, 15
sacks seal, & 8 5/8" plug.

Signed Walter L. Loh
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 PM Day: 20 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8"-254' w/180 sacks common, 4 1/2" set at 3639' w/
200 sacks common. Plugged back to 3569'. Top perf. at 3184'. Plugged
bottom w/5 sacks cement w/sand & 5 sacks cement on top to 3100'. Shot pipe
4 times & recovered 1715'. Ordered 165 sacks 50 premix-4 3/4" seal-3 3/4" lat. cl., 5 sacks balls,
15 sacks seal, & 8 5/8" plug. Pumped in 8 5/8" SP, 25 sacks cement, 5 sacks balls, 12
sacks seal, 70 sacks cement, 3 sacks seal, released plug & followed w/70 sacks
Cement. Maximum pressure 700 pounds.

Remarks: _____

STATE CORPORATION COMMISSION
RECEIVED
NOV 1 1982
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above plugging instructions were given as _____
and that I (did / did not) observe this plugging.

INVOICED

DATE 11-5-82

INV. NO. 1485-W

Signed Walter L. Loh
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82