

called 2-13-84

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20192-00-00

N/E, Sec. 34, T 9 S, R 15 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9100

Lease Name Winder Well # 1

Operator: B. & L. Oil Operation

County Osborne

Name & Address P. O. Box 250

Well Total Depth 3848 feet 125.06

Matoma Ks.

Conductor Pipe: Size _____ feet

913-885-4407 67651

Surface Casing: Size 8 7/8 feet 217

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Ranger Drilling License Number 6324

Address Box 856 Hays Ks.

Company to plug at: Hour: 11:30A Day: 13 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Frank Taggart

(company name) Ranger Drilg. (phone) _____

were: order 210 sx cem. 50/50 pozmix 6% gel 3% c.c. mixed with 2 sx Flow Seal - 1 sx hulls - 1.85/8 plug Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1994 Anhydrite 1207-46 Arbuckle. 3520

Dakota-1550

Signed Dale Z. Batthazor (TECHNICIAN)

444 = 750

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30P Day: 13 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT circ. @ 3520 Turn hole over

25 sx @ 3520

25 sx @ 1240

100 sx @ 750

40 sx @ 250 - 1 sx hulls push plug to 40'

10 sx @ 40

10 sx in Rat hole.

Remarks:

I did check Top Plug. cementing to sun.

I hereby certify that the above plugging instructions were given as herein stated and that I (did) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Dale Z. Batthazor (TECHNICIAN)

DATE 1-26-84 JAN 23 1984

01-23-1984

INV. NO. 9251-W CONSERVATION DIVISION Wichita, Kansas

RANGER DRILLING COMPANY, INC.

P.O. Box 856
Hays, Kansas 67601
913/825-4210

15-141-20192-00-00

DRILLERS LOG

OPERATOR: B & L OPERATIONS P.O. BOX 250 NATOMA, KS 67651	CONTRACTOR: RANGER DRILLING COMPANY, INC. P.O. BOX 856 HAYS, KS 67601
LEASE: WINDER #1	LOCATION: C-E/2-SW-NE Sec. 34-9S-15W Rooks County, Kansas
COMMENCED: 1-6-84	COMPLETED: 1-13-84
CASING: 8-5/8" @ 223'	STATUS: D & A
ELEVATION: 1994' K.B. 1989' G.L.	T.D.: 3849'

FORMATION DEPTHS

Surface Hole	0-223
Shale	223-1207
Anhydrite	1207-1246
Shale	1246-2380
Shale & Lime	2380-2565
Shale	2565-3045
Shale & Lime	3045-3195
Shale	3195-3275
Lime & Shale	3275-3342
Shale	3342-3444
Lime & Shale	3444-3490
Shale & Lime	3490-3569
Shale	3569-3849 R.T.D.

STATE OF KANSAS, COUNTY OF ELLIS, SS:


I, Robert R, Price, of the Ranger Drilling Company, Inc. state that the above and foregoing is a true and correct log of the above captioned well.

Robert R. Price
Robert R. Price *cm*

SUBSCRIBED and sworn to before me, this 23rd day of January, 1984.

My commission expires: May 2, 1987

Colleen Morain
Colleen Morain-Notary Public



RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1984
CONSERVATION DIVISION
Wichita, Kansas